

ADDENDUM NO. 2

CITY OF GOBLES

MEDC WATER MAIN IMPROVEMENTS PROJECT

Addendum No. 2 to the plans and specifications for the City of Gobles MEDC Water Main Improvements Project as prepared by Wightman & Associates, Inc. dated February, 2010

This Addendum No. 2 supplements and modifies the Contract Documents relating to the above referenced project. This Addendum shall be deemed a part of the Contract Documents, and to the extent that the provisions of the other Contract Documents are in conflict herewith, this Addendum shall control.

A) The Project Specification for Alternate #1, PS 23 shall be modified as follows:

All disturbed pavement areas due to construction of the water main will require full restoration consisting of 8 inches of aggregate base included in the water main items, one lift of HMA, 13A placed 2.5 inches thick (275 per syd) compacted flush with the existing pavement. The Asphalt performance grade shall remain P.G. 58-28. All materials, labor, construction methods, and pay items shall remain as called out in the contract documents.

A new Alternate #1 Proposal page P-3 is attached detailing the quantity changes.

The CONTRACTOR hereby acknowledges receipt of this Addendum No. 2 and shall include a signed copy with his bid.

Contractor: _____

By: _____

Title: _____

Date: _____

CITY OF GOBLES
MEDC WATER MAIN IMPROVEMENTS PROJECT
PROPOSAL

<i>ITEM NO</i>	<i>ESTIMATED QUANTITY</i>	<i>UNIT</i>	<i>DESCRIPTION</i>	<i>UNIT PRICE</i>	<i>TOTAL PRICE</i>
<u>Alternate #1</u>					
1	3,100	LFT	8" DIP Water Main		
2	70	LFT	6" DIP Water Main		
3	2,000	LBS	Compact Ductile Iron Fittings		
4	7	EA	8" Gate Valve & Box		
5	5	EA	6" Hydrant, Valve, & Box		
6	3	EA	Remove Existing Hydrant		
7	2	EA	Connect to Existing 6" Water Main		
8	2	EA	Connect to Existing 8" Water Main		
9	1	EA	Live Connection to Existing 10 Water Main		
10	36	EA	Reconnect 1" Water Service		
11	1,300	LFT	1" Water Service Pipe		
12	1	LS	Cul-De-Sac		
13	190	TON	HMA, 13A		
14	720	TON	HMA, 36A		
15	315	SFT	4" Concrete Sidewalk Replacement		
16	50	SFT	Sidewalk Ramp, ADA		
17	150	SYD	6" Concrete Drive Replacement		

FIRM: _____

TOTAL ALTERNATE #1 BID ENTERED \$ _____