

**ADDENDUM NO. 2**  
**NEW BUFFALO TOWNSHIP, MICHIGAN**  
**WATER AND SEWER SYSTEM IMPROVEMENTS PROJECT**

**OCTOBER 12, 2010**

**Contract B – LaPorte Road Sewer Improvements**

The following is Addendum No. 2 to the Plans and Specifications for the New Buffalo Township Water and Sewer System Improvements Project, as prepared by Wightman & Associates, Inc. Addendum No. 2 supplements and modifies the Contract Documents relating to the above referenced project. This Addendum shall be deemed a part of the Contract Documents, and to the extent that the provisions of the other Contract Documents are in conflict herewith, this Addendum shall control.

**Contract B – LaPorte Road Sewer Improvements**

1. The following description shall clarify backfill requirements for all sanitary sewer trenches within a future or proposed roadway, which includes the proposed development between LaPorte Road and Kinst Road.

*Backfill within all future and proposed roadways, both paved and unpaved, shall consist of MDOT Class II granular material or selected excavated material from the site that meets a 2% optimum moisture content as approved by the ENGINEER, placed in 12" layers and compacted to 95% Modified Proctor Density included in the respective sewer items. The ENGINEER shall perform periodic density tests to assure that the CONTRACTOR is meeting this requirement.*

The Contractor hereby acknowledges receipt of this Addendum No. 2 and shall include a signed copy with the bid.

\_\_\_\_\_  
Contractor

\_\_\_\_\_  
By

\_\_\_\_\_  
Title

\_\_\_\_\_  
Date